

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT



APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Deep Creek 6-22-4-2E				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT UNDESIGNATED				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR CRESCENT POINT ENERGY U.S. CORP						7. OPERATOR PHONE 720 880-3621				
8. ADDRESS OF OPERATOR 555 17th Street, Suite 750, Denver, CO, 80202						9. OPERATOR E-MAIL abaldwin@crecidentpointenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) Fee			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee') Lee Smith						14. SURFACE OWNER PHONE (if box 12 = 'fee') 801-322-1235				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee') 2400 Sunnyside, Salt Lake City, UT 84108						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input checked="" type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		1586 FNL 1726 FWL		SEnw	22	4.0 S	2.0 E	U		
Top of Uppermost Producing Zone		1586 FNL 1726 FWL		SEnw	22	4.0 S	2.0 E	U		
At Total Depth		1586 FNL 1726 FWL		SEnw	22	4.0 S	2.0 E	U		
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 1586			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 920			26. PROPOSED DEPTH MD: 7259 TVD: 7259				
27. ELEVATION - GROUND LEVEL 4935			28. BOND NUMBER LPM9080271			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
COND	24	16	0 - 40	65.0	H-40 ST&C	8.3	No Used	0	0.0	0.0
Surf	12.25	8.625	0 - 1000	24.0	J-55 ST&C	8.3	Class G	641	1.15	15.8
Prod	7.875	5.5	0 - 7259	17.0	N-80 LT&C	10.0	Light (Hibond)	159	4.31	10.5
							Class G	490	1.65	13.1
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input checked="" type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Emily Kate DeGrasse			TITLE Regulatory & Government Affairs Analyst			PHONE 720 880-3644				
SIGNATURE			DATE 11/08/2013			EMAIL edegrasse@crecidentpointenergy.com				
API NUMBER ASSIGNED 43047541920000			APPROVAL <div style="text-align: center;"> Permit Manager </div>							

RECEIVED: April 02, 2014

Crescent Point Energy U.S. Corp
Deep Creek 6-22-4-2E
 SE/NW of Section 22, T4S, R2E, USB&M
 SHL: 1586' FNL & 1726' FWL
 Uintah County, Utah

DRILLING PLAN

1-2. Geologic Surface Formation and Estimated Tops of Important Geologic Markers

Formation	Depth – TVD/MD
Uinta	Surface
Upper Green River Marker	3,214'
Mahogany	3,684'
Garden Gulch (TGR3)	4,703'
Douglas Creek	5,466'
Black Shale	5,966'
Castle Peak	6,216'
Uteland	6,508'
Wasatch	6,659'
TD	7,259'

3. Estimated Depths of Anticipated Water, Oil, Gas Or Minerals

Green River Formation (Oil) 3,214' – 6,659'

Wasatch Formation (Oil) 6,659' – 7,259'

Fresh water may be encountered in the Uinta Formation, but would not be expected below 350'. All usable (>10,000 PPM TDS) water and prospectively valuable minerals (as described by DOGM at onsite) encountered during drilling will be recorded by depth and adequately protected.

All water shows and water bearing geologic units will be reported to the geologic and engineering staff of the DOGM prior to running the next string of casing or before plugging orders are requested. Usage of the State of Utah form *Report of Water Encountered* is acceptable, but not required. All water shows must be reported within one (1) business day after being encountered. Detected water flows shall be sampled, analyzed, and reported to the geologic and engineering staff at the DOGM. The DOGM may request additional water samples for further analysis.

The following information is requested for water shows and samples where applicable:

Location & Sample Interval	Date Sampled
Flow Rate	Temperature
Hardness	pH
Water Classification (State of Utah)	Dissolved Calcium (Ca) (mg/l)
Dissolved Iron (Fe) (ug/l)	Dissolved Sodium (Na) (mg/l)
Dissolved Magnesium (Mg) (mg/l)	Dissolved Carbonate (CO ₃) (mg/l)
Dissolved Bicarbonate (NaHCO ₃) (mg/l)	Dissolved Chloride (Cl) (mg/l)
Dissolved Sulfate (SO ₄) (mg/l)	Dissolved Total Solids (TDS) (mg/l)

4. Proposed Casing & Cementing Program*Casing Design:*

Size	Interval		Weight	Grade	Coupling	Design Factors			
	Top	Bottom				Burst	Collapse	Tension	
Conductor 16" Hole Size 24"	0'	40'	65	H-40	STC	1,640	670	439	API
Surface casing 8-5/8" Hole Size 12-1/4"	0'	1000'	24	J-55	STC	2,950 405 7.27	1,370 696 1.97	244,000 24,000 10.17	API Load SF
Prod casing 5-1/2" Hole Size 7-7/8"	0'	7,259'	17	E-80	LTC	7,740 6,200 1.25	6,290 3,700 1.70	348,000 124,000 2.80	API Load SF

Assumptions:

1. Surface casing max anticipated surface pressure (MASP) = Frac gradient – gas gradient
2. Production casing MASP (production mode) = Pore pressure – gas gradient
3. All collapse calculations assume fully evacuated casing w/gas gradient
4. All tension calculations assume air weight

Frac gradient at surface casing shoe = 10.0 ppg
 Pore pressure at surface casing shoe = 8.33 ppg
 Pore pressure at prod casing shoe = 8.33 ppg
 Gas gradient = 0.115 psi/ft

Minimum Safety Factors:

Burst = 1.000
 Collapse = 1.125
 Tension = 1.800

All casing shall be new or, if used, inspected and tested. Used casing shall meet or exceed API standards for new casing.

All casing strings shall have a minimum of one (1) centralizer per joint on the bottom three joints.

Cementing Design:

Job	Fill	Description	Excess	Sacks	Weight (ppg)	Yield (ft ³ /sk)
Surface casing	1000' - surface	Class V 2% chlorides	75%	641	15.8	1.15
Prod casing Lead	3290' to Surface	Hifill Class V 3% chlorides	25% in open-hole, 0% in cased hole	159	10.5	4.31
Prod casing Tail	TD to 3290'	Class G 10% chlorides	15%	490	13.1	1.65

*Actual volume pumped will have excess over gauge hole or caliper log if available

- Compressive strength of tail cement: 500 psi @ 7 hours

Waiting On Cement: A minimum of four (4) hours shall elapse prior to attempting any pressure testing of the BOP equipment which would subject the surface casing cement to pressure, and a minimum of six (6) hours shall elapse before drilling out of the wiper plug, cement, or shoe. WOC time shall be recorded in the Driller's Log. Compressive strength shall be a minimum of 500 psi prior to drilling out.

The DOGM Roosevelt Field Office shall be notified, with sufficient lead time, in order to have a DOGM representative on location while running all casing strings and cementing.

The 8-5/8" surface casing shall in all cases be cemented back to surface. In the event that during the primary surface cementing operation the cement does not circulate to surface, or if the cement level should fall back more than 8 feet from surface, then a remedial surface cementing operation shall be performed to insure adequate isolation and stabilization of the surface casing.

The production casing cementing program shall be conducted as approved to protect and/or isolate all usable water zones, potentially productive zones, lost circulation zones, abnormally pressured zones, and any prospectively valuable deposits of minerals.

As a minimum, usable water zones shall be isolated and/or protected by having a cement top for the production casing at least 200 feet above the base of the usable water. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

Top plugs shall be used to reduce contamination of cement by displacement fluid. A Tuned spacer will be used to prevent contamination of the lead cement by the drilling mud.

All casing strings below the conductor shall be pressure tested to 0.22 psi per foot of casing string length or to 1500 psi, whichever is greater, but not to exceed 70% of the minimum internal yield. If pressure declines more than 10% in 30 minutes, corrective action shall be taken.

A Form 9, "Sundry Notices and Reports on Wells" shall be filed with the DOGM within 30 days after the work is completed. This report must include the following information:

Setting of each string of casing showing the size, grade, weight of casing set, depth, amounts and type of cement used, whether cement circulated of the top of the cement behind the casing,

depth of the cementing tools used, casing method and results, and the date of the work done. Spud date will be shown on the first reports submitted.

5. Drilling Fluids Program

The Conductor section (from 0' to 40') will be drilled by Auger and final depth determined by when the black shale is encountered with a minimum depth of 40'.

The surface interval will then be drilled to $\pm 1000'$ with air/mist system. The air rig is equipped with a 6 ½" blooie line that is straight run to the reserve pit. A variance is in request for this operation. The request can be found in Section 12 of this plan.

From $\pm 1000'$ to TD, a brine water system will be utilized. Clay inhibition and hole stability will be achieved with a polymer (DAP) additive; the reserve pit will be lined to address this additive. This brine water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 9.5 lbs/gal. If it is necessary to control formation fluids or pressure, the system will be weighted with the addition of brine, and if pressure conditions warrant, barite and/or calcium carbonate will be used as a weighting agent. There will be enough weighting agent on location to increase the entire system to 11.0 ppg MW.

No chromate additives will be used in the mud system on Federal and/or Indian lands without prior DOGM approval to ensure adequate protection of fresh water aquifers.

No chemicals subject to reporting under SARA Title III in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling, testing, or completing of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities, will be used, produced, stored, transported, or disposed of in association with the drilling, testing, or completing of this well.

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating characteristics of a hazardous waste will not be used in drilling, testing, or completion operations.

Crescent Point Energy will visually monitor pit levels and flow from the well during drilling operations.

6. Minimum Specifications for Pressure Control

A 3,000 psi BOP system or better will be used on this well. All equipment will be installed and tested per Onshore Order No. 2.

The configuration is as follows:

- Float in drillstring
- Inside BOP or safety valve
- Safety valve with same pipe threading
- Rotating Head below rotary table
- Fillup line
- 11" Annular Preventer – rated to 3,000 psi minimum
- 11" bore, 4-1/2" pipe ram – rated to 3,000 psi minimum
- 11" bore, Blind Ram – rated to 3,000 psi minimum
- 11" bore Drilling Spool with 2 side outlets (Choke side at 3" minimum & Kill side at 2" minimum)
 - 2 Kill line valves at 2" minimum – one with a check valve
 - Kill line at 2" minimum

- 2 Choke line valves at 3" minimum
- Choke line at 3" minimum
- 2 adjustable chokes on manifold
- Pressure gauge on choke manifold

7. BOPE Test Criteria

A Function Test of the Ram BOP equipment shall be made every trip and annular preventer every week. All required BOP tests and/or drills shall be recorded in the Driller's Report.

Chart recorders will be used for all pressure tests. Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to DOGM representatives upon request.

At a minimum, the Annular preventer will be tested to 50% of its rating for ten minutes. All other equipment (Rams, valves, manifold) will be tested at 3,000 psi for 10 minutes with a test plug. If rams are to be changed for any reason post drillout, the rams will be tested to 70% of surface casing internal yield.

At a minimum, the above pressure tests will be performed when such conditions exist:

- BOP's are initially installed
- Whenever a seal subject to pressure test is broken
- Following repairs to the BOPs
- Every 30 days

8. Accumulator

The Accumulator will have sufficient capacity to open the hydraulically-controlled choke line valve (HCR), close both rams and annular preventer as well maintain 200 psi above nitrogen precharge of the accumulator without use of accumulator pumps. The fluid reservoir volume will be double the usable volume of the accumulator system. The fluid level will be maintained per manufacturer's specifications.

The BOP system will have two independent power sources to close both rams and annular preventer, while opening HCR. Nitrogen bottles will be one source and electric and/or air powered pumps will be the other.

The accumulator precharge will be conducted every 6 months and maintained to be within the specifications of Onshore Order No. 2

A manual locking device or automatic locking device will be installed on both ram preventers and annular preventer.

Remote controls will be readily accessible to the driller and be capable of closing all preventers. Main controls will be available to allow full functioning of all preventers and HCR.

9. Testing, Logging and Coring Programs

The logging program will consist of a Gamma Ray log from TD to base of surface casing @ +/- 1100'. A cement bond log will be run from PBTD to top of cement. No drill stem testing or coring is planned for this well.

10. Anticipated Abnormal Pressures or Temperature

No abnormal temperatures or pressures are anticipated. No hydrogen sulfide has been encountered or is known to exist from previous wells drilled to similar depths in this area.



Maximum anticipated bottomhole pressure will be approximately equal to total depth in feet multiplied by a 0.52 psi/ft gradient, and a maximum anticipated surface pressure will be approximately equal to the bottomhole pressure calculated minus the pressure of a partially evacuated hole calculated at a 0.22 psi/foot gradient.

11. Anticipated Starting Date and Duration of Operations

It is anticipated that drilling operations will commence in September 2014, and take approximately seven (7) days from spud to rig release and two weeks for completions.

12. Variances Requested from Onshore Order No. 2

1. A diverter is utilized for surface air drilling, rather than a lubricated rotating head.
2. The blooie line is 45 ft from the wellbore rather than 100 ft and is not anchored down.
3. The blooie line is not equipped with an automatic igniter or continuous pilot light.
4. The compressor is located on the rig itself and not 100 ft from the wellbore.
5. The requirement for an Formation Integrity Test (FIT) or a Leak Off Test (LOT)

R. 2 E.SCALE 1" = 1000'
GRID NORTH**T. 4 S.****SHL**

LATITUDE (NAD 83)
NORTH 40.125067 DEG.
LONGITUDE (NAD 83)
WEST 109.757409 DEG.

LATITUDE (NAD 27)
NORTH 40.125104 DEG.
LONGITUDE (NAD 27)
WEST 109.756712 DEG.

NORTHING
657364.79

EASTING
2487451.17'


DATUM
SPCS UTC (NAD 27)

SURVEYOR'S STATEMENT

I, DAVID E. HENDERAHAN, OF GRAND JUNCTION, COLORADO, HEREBY STATE: THIS MAP WAS MADE FROM NOTES TAKEN DURING AN ACTUAL FIELD SURVEY DONE UNDER MY DIRECT SUPERVISION ON THE 9th DAY OF AUGUST, 2013 AND THAT THIS PLAT CORRECTLY SHOWS THE LOCATION OF DEEP CREEK 6-22-4-2E AS STAKED ON THE GROUND.

LEGEND

- ◆ WELL LOCATION
- BOTTOM HOLE LOC. (APPROX)
- FOUND MONUMENT
- ▲ PREVIOUSLY FOUND MONUMENT



DRG RIFFIN & ASSOCIATES, INC.
(307) 362-5028 1414 ELK ST., ROCK SPRINGS, WY 82901

DRAWN: 9/18/13 - DEH

SCALE: 1" = 1000'


REVISED: N/A -.

DRG JOB No. 20029

EXHIBIT 1-1

**PLAT OF DRILLING LOCATION IN
SENECA, SECTION 22, FOR
CRESCENT POINT ENERGY**

**1586' F/NL, & 1726' F/WL, SECTION 22,
T. 4 S., R. 2 E., U.S.M.,
UINTAH COUNTY, UTAH**



1414 ELK ST., ROCK SPRINGS, WY 82901


SCALE: 1" = 1 MILE

DRG JOB No. 20029

TOPO A - 1 OF 2

PROPOSED ROAD

EXISTING ROAD



1414 ELK ST., ROCK SPRINGS, WY 82901

SCALE: 1" = 1 MILE


DRG JOB No. 20029


TOPO A - 2 OF 2


***PROPOSED ACCESS FOR
CRESCENT POINT ENERGY
DEEP CREEK 6-22-4-2E
SECTION 22, T.4 S., R.2 E.***

PROPOSED ROAD

EXISTING ROAD



 DRG RIFFIN & ASSOCIATES, INC. (307) 362-5028 1414 ELK ST., ROCK SPRINGS, WY 82901		ONE MILE RADIUS FOR CRESCENT POINT ENERGY DEEP CREEK 6-22-4-2E SECTION 22, T. 4 S., R. 2 E.	
DRAWN: 8/26/2013 - RAS		SCALE: 1" = 2000'	
REVISED: N/A -		DRG JOB No. 20029	
		TOPO C	
		PROPOSED ROAD ————	EXISTING ROAD ————


RIFFIN & ASSOCIATES, INC.

(307) 362-5028

1414 ELK ST., ROCK SPRINGS, WY 82901

DRAWN: 8/26/2013 - RAS

SCALE: 1" = 2000'

REVISED: N/A -

DRG JOB No. 20029

TOPO D

PROPOSED PIPELINE FOR
CRESCENT POINT ENERGY
DEEP CREEK 6-22-4-2E
SECTION 22, T. 4 S., R. 2 E.

TOTAL PROPOSED LENGTH: 207.9±

PROPOSED PIPELINE

EXISTING ROAD

RECEIVED: November 08, 2013

MEMORANDUM of SURFACE USE AGREEMENT and GRANT OF EASEMENTS

David Eckelberger is Landman for Ute Energy LLC and Ute Energy Upstream Holdings LLC, authorized to do business in Utah (hereinafter referred to as "Ute Energy"). Ute Energy owns, operates and manages oil and gas interests in Uintah and Duchesne Counties, Utah.

WHEREAS, that certain Surface Use Agreement and Grant of Easements ("Agreement") dated effective June 2nd, 2011 has been entered into by and between Deep Creek Investments, whose address is c/o Lee M. Smith, General Partner, 2400 Sunnyside, Salt Lake City, Utah 84108 ("Owner") and Ute Energy, whose address is 1875 Lawrence Street, Suite 200, Denver, CO 80202 ("Operator").

WHEREAS, Owner owns the surface estate of the real property in Uintah County, Utah (the "Property"), legally described as:

Township 4 South, Range 2 East, USM

Section 9: S/2, NE/4

Section 10: W/2W/2

Section 15: S/2

Section 16: N/2

Section 22: All

Entry 2011004320
Book 1239 Page 57 \$14.00
16-JUN-11 09:00
RANDY SIMMONS
RECORDER, UTAH COUNTY, UTAH
UTE ENERGY
PO BOX 789 FT DUCHESNE, UT 84026
Rec By: DEBRA ROOKS, DEPUTY

WHEREAS, for an agreed upon monetary consideration, Operator may construct the necessary well site pads for drilling, completion, re-completion, reworking, re-entry, production, maintenance and operation of wells ("Well Pads") on the Property. Ute Energy, its agents, employees, assigns, contractors and subcontractors, may enter upon and use the Well Pads for the purposes of drilling, completing, producing, maintaining, and operating Wells to produce oil, gas and associated hydrocarbons produced from the Property, including the construction and use of frac pits, tank batteries, water disposal pits, production equipment, compressor sites and other facilities used to produce and market the oil, gas and associated hydrocarbons.


WHEREAS, Operator has the right to a non-exclusive access easement ("Road Easement") on the Property for ingress and egress by Operator and its employees, contractors, sub-contractors, agents, and business invitees as needed to conduct oil and gas operations.

WHEREAS, Operator, its employees, contractors, sub-contractors, agents and business invitees has the right to a non-exclusive pipeline easement to construct, maintain, inspect, operate and repair a pipeline or pipelines, pigging facilities and related appurtenances for the transportation of oil, gas, petroleum products, water and any other substances recovered during oil and gas production.

WHEREAS, this Agreement shall run with the Property and be binding upon and inure to the benefit of the parties and their respective heirs, successors and assigns as stated in this Agreement.

THEREFORE, Operator is granted access to the surface estate and the Agreement constitutes a valid and binding surface use agreement as required under Utah Admin. Code Rule R649-3-34(7).

This Memorandum is executed this 14th day of June, 2011


David Eckelberger
Landman

STATE OF COLORADO)
COUNTY OF DENVER) ss

The foregoing instrument was acknowledged before me by David Eckelberger, Landman for Ute Energy LLC and Ute Energy Upstream Holdings LLC this 14th day of June, 2011.

Notary Seal:


Notary Public

My Commission expires:

September 15, 2014
Date



My Comm. Expires September 15, 2014




519 E. 300 S.
Vernal, UT 84078
P435-781-0434
F435-789-5656

Oct, 18, 2013



**9.5" TIME SAVER WELLHEAD SYSTEM
WITH DRILL SPOOL,
AND BOP CONFIGURATION**





555 17th Street, Suite 750
Denver, CO 80202
Phone: (720) 880-3610

November 6, 2013

State of Utah Division of Oil, Gas and Mining
Attention: Diana Mason
1594 West North Temple
Salt Lake City, UT 84116

RE: Exception Location Request (R649-3-3)
Deep Creek 6-22-4-2E
SE/NW of Section 22, T4S, R2E
1586' FNL & 1726' FWL
UBS&M, Uintah County, Utah

Dear Ms. Mason:

Please be advised that Crescent Point Energy U.S. Corp (Crescent Point) is requesting approval from the Utah Division of Oil, Gas and Mining for the captioned well that has a surface and bottom hole location of 1586' FNL & 1726' FWL of Section 22, Township 4S, Range 2E, USB&M, Uintah County, Utah. A copy of the survey plat is included in the APD package for your reference. This well was moved outside of the legal window from the center of the quarter quarter due to topographical constraints.

Please be advised that Crescent Point has obtained written consent from 100% of the oil and gas owners within a radius of 460' along the intended wellbore.


If you have any questions or need further information, please contact myself or Lori Browne at 720-880-3610.

Sincerely,
Crescent Point Energy U.S. Corp

Ryan Waller

Ryan Waller
Landman

RECEIVED: November 08, 2013



(307) 362-5028

RIFFIN & ASSOCIATES, INC.
 1414 ELK ST., ROCK SPRINGS, WY 82901

DRAWN: 8/26/2013 - RAS

SCALE: 1" = 60'


REVISED: N/A - .

DRG JOB No. 20029

FIGURE 1


CRESCENT POINT ENERGY
DEEP CREEK 6-22-4-2E
SECTION 22, T. 4 S., R. 2 E.


UNGRADED ELEVATION: 4936.1
 FINISHED ELEVATION: 4935.2







**BEFORE DIGGING
CALL FOR
UTILITY LINE LOCATION**

NOTE: THE EARTH QUANTITIES ON
THIS DRAWING ARE ESTIMATED
AND THE USE OF THIS IS AT THE
RESPONSIBILITY OF THE USER.



 RIFFIN & ASSOCIATES, INC. (307) 362-5028 1414 ELK ST., ROCK SPRINGS, WY 82901		PAD LAYOUT CRESCENT POINT ENERGY DEEP CREEK 6-22-4-2E SECTION 22, T. 4 S., R. 2 E.
DRAWN: 8/26/2013 - RAS	SCALE: 1" = 60'	UNGRADED ELEVATION: 4936.1 FINISHED ELEVATION: 4935.2
REVISED: N/A - .	DRG JOB No. 20029	
	FIGURE 1A	

**3+50****2+75****2+12****0+00****RIFFIN & ASSOCIATES, INC.**

(307) 362-5028

1414 ELK ST., ROCK SPRINGS, WY 82901

DRAWN: 8/26/2013 - RAS

SCALE: HORZ 1" = 50' VERT 1" = 10'

REVISED: N/A -


DRG JOB No. 20029

FIGURE 2

CRESCENT POINT ENERGY
DEEP CREEK 6-22-4-2E
SECTION 22, T. 4 S., R. 2 E.

UNGRADED ELEVATION: 4936.1
 FINISHED ELEVATION: 4935.2

RECEIVED: November 08, 2013




DRG **RIFFIN & ASSOCIATES, INC.**
 (307) 362-5028 1414 ELK ST., ROCK SPRINGS, WY 82901

CRESCENT POINT ENERGY
DEEP CREEK 6-22-4-2E
SECTION 22, T. 4 S., R. 2 E.

ESTIMATED EARTHWORK

		ITEM	CUT	FILL	TOPSOIL	EXCESS
DRAWN: 8/26/2013 - RAS	SCALE: 1" = 60'	PAD	2,242 CY	1,090 CY	1,152 CY	0 CY
REVISED: N/A -	DRG JOB No. 20029	PIT	1,941 CY			1,941 CY
	FIGURE 3	TOTALS	4,183 CY	1,090 CY	1,152 CY	1,941 CY

RECEIVED: November 08, 2013



API Number: 4304754192

Well Name: Deep Creek 6-22-4-2E



Township: T04.0S Range: R02.0E Section: 22 Meridian: U

Operator: CRESCENT POINT ENERGY U.S. CORP

Map Prepared: 11/12/2013
Map Produced by Diana Mason

Wells Query		Units	
Status		STATUS	
APD - Approved Permit		ACTIVE	
DRL - Spudded (Drilling Commenced)		EXPLORATORY	
GRW - Gas Injection		GAS STORAGE	
GS - Gas Storage		NF PP OIL	
LOC - New Location		NF SECONDARY	
OPS - Operation Suspended		PI OIL	
PA - Plugged Abandoned		PP GAS	
PGW - Producing Gas Well		PP GEOTHERML	
POW - Producing Oil Well		PP OIL	
SGW - Shut-in Gas Well		SECONDARY	
SOW - Shut-in Oil Well		TERMINATED	
TA - Temp. Abandoned			
TW - Test Well			
WOW - Water Disposal			
WW - Water Injection Well			
WSW - Water Supply Well			

Fields	
STATUS	
Unknown	
ABANDONED	
ACTIVE	
COMBINED	
INACTIVE	
STORAGE	
TERMINATED	



Well Name	CRESCENT POINT ENERGY U.S. CORP Deep Creek 6-22-4-2E 430475			
String	Cond	Surf	Prod	
Casing Size(in)	16.000	8.625	5.500	
Setting Depth (TVD)	40	1000	7259	
Previous Shoe Setting Depth (TVD)	0	40	1000	
Max Mud Weight (ppg)	8.3	8.3	10.0	
BOPE Proposed (psi)	0	500	3000	
Casing Internal Yield (psi)	1000	2950	7740	
Operators Max Anticipated Pressure (psi)	3775		10.0	

Calculations	Cond String	16.000	"	
Max BHP (psi)	.052*Setting Depth*MW=	17		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	12	NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	8	NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	8	NO	
Required Casing/BOPE Test Pressure=		40	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		0	psi *Assumes 1psi/ft frac gradient	


Calculations	Surf String	8.625	"	
Max BHP (psi)	.052*Setting Depth*MW=	432		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	312	YES	air/mist
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	212	YES	OK
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	221	NO	OK
Required Casing/BOPE Test Pressure=		1000	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		40	psi *Assumes 1psi/ft frac gradient	

Calculations	Prod String	5.500	"	
Max BHP (psi)	.052*Setting Depth*MW=	3775		
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	2904	YES	3M BOPE & annular, rotating head, blind ram,
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	2178	YES	pipe rams, kill & choke lines
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	2398	NO	OK
Required Casing/BOPE Test Pressure=		3000	psi	
*Max Pressure Allowed @ Previous Casing Shoe=		1000	psi *Assumes 1psi/ft frac gradient	

Calculations	String		"	
Max BHP (psi)	.052*Setting Depth*MW=			
			BOPE Adequate For Drilling And Setting Casing at Depth?	
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO	
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO	
			*Can Full Expected Pressure Be Held At Previous Shoe?	
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO	
Required Casing/BOPE Test Pressure=			psi	
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient	

43047541920000 Deep Creek 6-22-4-2E

Casing Schematic



Well name:	43047541920000 Deep Creek 6-22-4-2E	
Operator:	CRESCENT POINT ENERGY U.S. CORP	
String type:	Surface	Project ID: 43-047-54192
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 8.300 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 88 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 100 ft

Cement top: Surface

Burst

Max anticipated surface pressure: 880 psi
Internal gradient: 0.120 psi/ft
Calculated BHP 1,000 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.70 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Tension is based on buoyed weight.
Neutral point: 875 ft

Non-directional string.**Re subsequent strings:**

Next setting depth: 7,259 ft
Next mud weight: 10.000 ppg
Next setting BHP: 3,771 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 1,000 ft
Injection pressure: 1,000 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1000	8.625	24.00	J-55	ST&C	1000	1000	7.972	5147
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	431	1370	3.178	1000	2950	2.95	21	244	11.62 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801-538-5357
FAX: 801-359-3940

Date: March 31, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 1000 ft, a mud weight of 8.3 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Well name:	43047541920000 Deep Creek 6-22-4-2E	
Operator:	CRESCENT POINT ENERGY U.S. CORP	
String type:	Production	Project ID: 43-047-54192
Location:	UINTAH COUNTY	

Design parameters:**Collapse**

Mud weight: 10.000 ppg
Design is based on evacuated pipe.

Minimum design factors:**Collapse:**

Design factor 1.125

Environment:

H2S considered? No
Surface temperature: 74 °F
Bottom hole temperature: 176 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 1,000 ft

Burst:

Design factor 1.00

Cement top: Surface

Burst

Max anticipated surface pressure: 2,174 psi
Internal gradient: 0.220 psi/ft
Calculated BHP 3,771 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.60 (B)

Non-directional string.

Tension is based on buoyed weight.
Neutral point: 6,158 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	7259	5.5	17.00	E-80	LT&C	7259	7259	4.767	239547
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	3771	6290	1.668	3771	7740	2.05	104.7	320	3.06 J

Prepared Helen Sadik-Macdonald
by: Div of Oil, Gas & Mining

Phone: 801 538-5357
FAX: 801-359-3940

Date: March 31, 2014
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 7259 ft, a mud weight of 10 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator CRESCENT POINT ENERGY U.S. CORP
Well Name Deep Creek 6-22-4-2E
API Number 43047541920000 **APD No** 9041 **Field/Unit** UNDESIGNATED
Location: 1/4,1/4 SENW Sec 22 Tw 4.0S Rng 2.0E 1586 FNL 1726 FWL
GPS Coord (UTM) 605889 4442339 **Surface Owner** Lee Smith

Participants

Jim Burns - Starpoint, Lori Browne, Brian Foote, Mahe Taufu - Crescent Point; Mark Hecksel-DRGriffin; Allan Smith - landowner

Regional/Local Setting & Topography

Location is in the Deep Creek area in an historic floodplain below two benches Known as the Leland bench in Uintah County. The region is deeply incised and eroded clay sediments surrounded by a bench and the occassional butte with sandstone caps. The area has traditionally been used for Spring graze for sheep but, has seen heavy development for petroleum extraction. The ground is rather bare of vegetation and wildlife sightings are rare. Numerous drainages though shallow and ephemeral are noted throughout the region.

Surface Use Plan

Current Surface Use
Grazing

New Road Miles	Well Pad	Src Const Material	Surface Formation
0.04	Width 150 Length 350	Onsite	UNTA

Ancillary Facilities

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands Y

Flora / Fauna

High desert shrubland ecosystem. Expected vegetation consists of black sagebrush, shadscale, Atriplex spp., mustard spp, rabbit brush, horsebrush, broom snakeweed, Opuntia spp and spring annuals.

Dominant vegetation;

Gardiner's atriplex

Wildlife;

Adjacent habitat contains forbs that may be suitable browse for deer, antelope, prairie dogs or rabbits, though none were observed.

Soil Type and Characteristics

light colored clayey sediments

Erosion Issues Y

Sedimentation Issues Y**Site Stability Issues N****Drainage Diversion Required? Y****Berm Required? Y****Erosion Sedimentation Control Required? N****Paleo Survey Run? N Paleo Potential Observed? N Cultural Survey Run? N Cultural Resources? N****Reserve Pit****Site-Specific Factors****Site Ranking****Distance to Groundwater (feet)** 100 to 200 5**Distance to Surface Water (feet)** >1000 0**Dist. Nearest Municipal Well (ft)** >5280 0**Distance to Other Wells (feet)** >1320 0**Native Soil Type** Mod permeability 10**Fluid Type** Fresh Water 5**Drill Cuttings** Normal Rock 0**Annual Precipitation (inches)** 0**Affected Populations****Presence Nearby Utility Conduits** Not Present 0**Final Score** 20 1 Sensitivity Level**Characteristics / Requirements**

A 60' x 100' x 12' deep reserve pit is planned in an area of cut on the northwest side of the location. A pit liner is required. Operator commonly uses a 16 mil liner with a felt underliner. Pit should be fenced to prevent entry by deer, other wildlife and domestic animals. A minimum freeboard of two feet shall be maintained at all times. Pit to be closed within one year after drilling activities are complete.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 16 Pit Underlayment Required? N**Other Observations / Comments**

pad situated between to outcroppings and pretty flat. # drainages exist across pad. Plans show diversion for these

Chris Jensen
Evaluator

1/29/2014
Date / Time

Application for Permit to Drill

Statement of Basis

Utah Division of Oil, Gas and Mining

APD No	API WellNo	Status	Well Type	Surf Owner	CBM
9041	43047541920000	LOCKED	OW	P	No
Operator	CRESCENT POINT ENERGY U.S. CORP		Surface Owner-APD	Lee Smith	
Well Name	Deep Creek 6-22-4-2E		Unit		
Field	UNDESIGNATED		Type of Work	DRILL	
Location	SENW 22 4S 2E U 1586 FNL 1726 FWL GPS Coord (UTM) 605888E 4442340N				

Geologic Statement of Basis

Crescent Point proposes to set 40' of conductor and 1,000' of surface casing at this location. The base of the moderately saline water at this location is estimated to be at a depth of 900'. A search of Division of Water Rights records shows 1 water well within a 10,000 foot radius of the center of Section 22. This well is located in the SE/4 of Section 14. Depth is listed as 966 feet. Listed uses are irrigation, domestic and stock watering. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement should adequately protect ground water in this area.

Brad Hill
APD Evaluator

2/13/2014
Date / Time

Surface Statement of Basis

Location is proposed in a good location although outside the spacing window. Well is to be drilled directionally. Access road enters the pad from the North. The landowner or its representative was in attendance for the pre-site inspection.

The soil type and topography at present do combine to pose a significant threat to erosion or sediment/ pollution transport in these regional climate conditions.

Usual construction standards of the Operator appear to be adequate for the proposed purpose as submitted. Plans include measures for the diversion of drainages and pad footprint has been modified to lessen disturbance to these. Reserve pit is in an area of cut. I quickly recognize no special flora or animal species or cultural resources on site that the proposed action may harm. A riparian area (Deep Creek) can be found adjacent the site to the North. The location was not previously surveyed for cultural and paleontological resources (as the operator saw fit). I have advised the operator take all measures necessary to comply with ESA and MBTA and that actions insure no disturbance to species that may have not been seen during onsite visit.

The location should be bermed to prevent fluids from entering or leaving the confines of the pad. Fencing around the reserve pit will be necessary to prevent wildlife and livestock from entering. A synthetic liner of 16 mils (minimum) should be utilized in the reserve pit. Measures (BMP's) shall be taken to protect steep slopes and topsoil pile from erosion, sedimentation and stability issues. A diversion is to be built sufficient to conduct overland or channel flow from a natural channel west of the pad between corners 4 and 2, around the corner North and past marker 1 to reintroduce flows back into the natural channel offsite.

Chris Jensen
Onsite Evaluator

1/29/2014
Date / Time

Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A synthetic liner with a minimum thickness of 16 mils with a felt subliner shall be properly installed and maintained in the reserve pit.
Surface	Drainages adjacent to the proposed pad shall be diverted around the location.
Surface	The well site shall be bermed to prevent fluids from entering or leaving the pad.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

CONFIDENTIAL

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 11/8/2013

API NO. ASSIGNED: 43047541920000

WELL NAME: Deep Creek 6-22-4-2E

OPERATOR: CRESCENT POINT ENERGY U.S. CORP (N3935)

PHONE NUMBER: 720 880-3644

CONTACT: Emily Kate DeGrasse

PROPOSED LOCATION: SENW 22 040S 020E

Permit Tech Review: ☒

SURFACE: 1586 FNL 1726 FWL

Engineering Review: ☒

BOTTOM: 1586 FNL 1726 FWL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.12472

LONGITUDE: -109.75726

UTM SURF EASTINGS: 605888.00

NORTHINGS: 4442340.00

FIELD NAME: UNDESIGNATED

LEASE TYPE: 4 - Fee

LEASE NUMBER: Fee

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 4 - Fee

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: STATE - LPM9080271☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☒ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☒ R649-3-3. Exception☒ Drilling Unit

Board Cause No: R649-3-3

Effective Date:

Siting:

☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 1 - Exception Location - dmason
5 - Statement of Basis - bhill
12 - Cement Volume (3) - ddoucet
23 - Spacing - dmason
25 - Surface Casing - hmacdonald

RECEIVED: April 02, 2014



GARY R. HERBERT
Governor

SPENCER J. COX
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Deep Creek 6-22-4-2E

API Well Number: 43047541920000

Lease Number: Fee

Surface Owner: FEE (PRIVATE)

Approval Date: 4/2/2014

Issued to:

CRESCENT POINT ENERGY U.S. CORP, 555 17th Street, Suite 750, Denver, CO 80202

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-3. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled, completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Cement volume for the 5 1/2" production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to surface and tail brought to above the top of the Green River Formation.

Surface casing shall be cemented to the surface.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan - contact Dustin Doucet
- Significant plug back of the well - contact Dustin Doucet
- Plug and abandonment of the well - contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels
OR
submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website
at <http://oilgas.ogm.utah.gov>
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program
- contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well - contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 - office
- Dustin Doucet 801-538-5281 - office
801-733-0983 - after office hours
- Dan Jarvis 801-538-5338 - office
801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation

- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "J. Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well	8. WELL NAME and NUMBER: Deep Creek 6-22-4-2E	
2. NAME OF OPERATOR: CRESCENT POINT ENERGY U.S. CORP	9. API NUMBER: 43047541920000	
3. ADDRESS OF OPERATOR: 555 17th Street, Suite 750 , Denver, CO, 80202	PHONE NUMBER: 720 880-3621 Ext	9. FIELD and POOL or WILDCAT: UNDESIGNATED
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1586 FNL 1726 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 22 Township: 04.0S Range: 02.0E Meridian: U	COUNTY: UINTAH	
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 6/9/2014	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input type="text"/>

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Crescent Point Energy US Corp spud the Deep Creek 6-22-4-2E with
 Pete Martin Drilling Rig 11 on June 9, 2014 at 10am.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 June 13, 2014

NAME (PLEASE PRINT) Emily Kate DeGrasse	PHONE NUMBER 720 880-3644	TITLE Regulatory & Government Affairs Analyst
SIGNATURE N/A		DATE 6/10/2014

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: CRESCENT POINT ENERGY U.S. CORP		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 555 17th Street, Suite 750 , Denver, CO, 80202		8. WELL NAME and NUMBER: Deep Creek 6-22-4-2E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1586 FNL 1726 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 22 Township: 04.0S Range: 02.0E Meridian: U		9. API NUMBER: 43047541920000
PHONE NUMBER: 720 880-3621 Ext		9. FIELD and POOL or WILDCAT: UNDESIGNATED
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 9/2/2014	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Attached please find drilling report for Crescent Point Energy's Deep Creek 6-22-4-2E, encompassing all drilling activities to date.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 02, 2014		
NAME (PLEASE PRINT) Lauren MacMillan	PHONE NUMBER 303 382-6787	TITLE Regulatory Specialist
SIGNATURE N/A	DATE 9/2/2014	



Daily Drilling Report

Report for: 8/25/2014
Report #: 1.0, DFS: 0.13
Depth Progress: 0.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192		Surface Legal Location 6-22-4-2		License # FEE	
Spud Date 6/9/2014 10:00		Date TD Reached (wellbore)		Rig Release Date 9/2/2014 06:00	
				Ground Elevation (ft) 4,935.00	
				Orig KB Elev (ft) 4,947.00	
Completion Type					
Weather		Temperature (°F)		Road Condition	
				Hole Condition	
Operation At 6am W.O.Drilling Rig		Operation Next 24hrs			
24 Hr Summary MIRU PETE MARTIN RIG #11 ,DRILL 52' KB 24" COND. HOLE,RUN & CEMENT 52' KB 16" COND. PIPE,Cmt.To Surf. With ReadyMix RDMO SPUD @10:00 6/09/2014MIRU Pro Petro Rig #10, Drill 1032' KB 12 1/4" Surface hole,R/U & run 1013' KB 8 5/8" 24# surface CSG,Cement W/675 sks 15.8 ppg 1.15 cuft/sk yield cement,25 bbls good cement T/Surf,cement stayed @ Surf,R/D cementers,wait on drilling rig					
Time Log					
Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity
					Com
Mud Checks					
<depth>ftKB, <dtm>					
Type	Time	Depth (ftKB)	Density (lb/gal)	Funnel Viscosity (s/qt)	PV Override (cP)
YP OR (lb/100ft²)					
Gel 10 sec (lb/100ft²)	Gel 10 min (lb/100ft²)	Filtrate (mL/30min)	Filter Cake (1/32")	pH	Sand (%)
					Solids (%)
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L)	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)
					Gel 30 min (lb/100ft²)
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)	
Drill Strings					
BHA #1, Kick Off					
Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8
Nozzles (1/32") 16/16/16/16/16/16		String Length (ft) 583.98		Max Nominal OD (in) 6.500	
String Components SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP					
Comment Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)					
Drilling Parameters					
Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)
					Q Flow (gpm)
					WOB (1000lbf)
					RPM (rpm)
					SPP (psi)
					Drill Str Wt (1000lbf)
					PU Str Wt (1000lbf)
					Drill Tq
Original Hole	1,020.0	1,020.0			

AFE Number 1753213US		
Start Depth (ftKB) 1,020.0	End Depth (ftKB) 1,020.0	
Target Formation WASATCH	Target Depth (ftKB) 7,259.0	
Last Casing String Surface, 1,013.0ftKB		
Daily Contacts		
Job Contact	Mobile	
Rigs		
Capstar, 316		
Contractor Capstar	Rig Number 316	
Rig Supervisor JAKE	Phone Mobile 713-481-7601	
<des>, <make>, <model>		
Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...
P (psi)	Slow Spd	Strokes (s...
		Eff (%)
Mud Additive Amounts		
Des	Field Est (Cost/unit)	Consumed
Barite	10.65	304.0
Engineering	450.00	1.0
Rental	50.00	1.0
Safety Checks		
Time	Type	Des
Wellbores		
Wellbore Name	KO MD (ftKB)	
Original Hole		



Daily Drilling Report

Report for: 8/25/2014
Report #: 2.0, DFS: 0.13
Depth Progress: 0.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192	Surface Legal Location 6-22-4-2	License # FEE
Spud Date 6/9/2014 10:00	Date TD Reached (wellbore)	Rig Release Date 9/2/2014 06:00
	Ground Elevation (ft) 4,935.00	Orig KB Elev (ft) 4,947.00

Completion Type

Weather RAINING	Temperature (°F) 66.0	Road Condition FAIR	Hole Condition Good
--------------------	--------------------------	------------------------	------------------------

Operation At 6am
TEST BOPS

Operation Next 24hrs
PICK UP BHA & DRILL OUT

24 Hr Summary
WAIT ON LOCATION BLADE OFF MUD & HAUL IN ROCK / MOVE IN RIG UP NIPPLE UP & TEST BOPS

Time Log

Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com
06:00	13:00	7.00	7.00	1	RIGUP & TEARDOWN	WAIT ON LOCATION HAULING IN ROCK
13:00	23:00	10.00	17.00	1	RIGUP & TEARDOWN	MOVE IN RIG UP CAPSTAR # 316
23:00	03:00	4.00	21.00	14	NIPPLE UP B.O.P	NIPPLE UP BOPS
03:00	06:00	3.00	24.00	15	TEST B.O.P	TEST BOPS PIPE BLINES & CHOKE ALL 3000 PSI F/ 10 MIN ANN 1500 F/ 10 MIN & CASING 1500 F/ 30 MINS

Mud Checks

<depth>ftKB, <dtm>

Type	Time	Depth (ftKB)	Density (lb/gal)	Funnel Viscosity (s/qt)	PV Override (cP)	YP OR (lb/100ft²)
Gel 10 sec (lb/100ft²)	Gel 10 min (lb/100ft²)	Filtrate (mL/30min)	Filter Cake (1/32")	pH	Sand (%)	Solids (%)
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L)	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)

Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)
-----------------------	------------------------	---------------------------	--------------------------	-------------------------

Drill Strings

BHA #1, Kick Off

Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8
--------------	--------------------------------------	---------------------	---------------------------------	------------------------------	--------------------

Nozzles (1/32") 16/16/16/16/16	String Length (ft) 583.98	Max Nominal OD (in) 6.500
-----------------------------------	------------------------------	------------------------------

String Components
SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP

Comment
Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)

Drilling Parameters

Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq
Original Hole	1,020.0	1,020.0										

AFE Number
1753213US

Start Depth (ftKB) 1,020.0	End Depth (ftKB) 1,020.0
-------------------------------	-----------------------------

Target Formation WASATCH	Target Depth (ftKB) 7,259.0
-----------------------------	--------------------------------

Last Casing String
Surface, 1,013.0ftKB

Daily Contacts

Job Contact	Mobile
Floyd Mitchell	823-3608
DOUG HACKFORD	970-640-3882

Rigs

Capstar, 316

Contractor Capstar	Rig Number 316
Rig Supervisor JAKE	Phone Mobile 713-481-7601

<des>, <make>, <model>

Pump #	Pwr (hp)	Rod Dia (in)
--------	----------	--------------

Liner Size (in)	Stroke (in)	Vol/Stk OR (b...
-----------------	-------------	------------------

P (psi)	Slow Spd	Strokes (s...)	Eff (%)
---------	----------	----------------	---------

Mud Additive Amounts

Des	Field Est (Cost/unit)	Consumed
Barite	10.65	304.0
Engineering	450.00	1.0
Rental	50.00	1.0

Safety Checks

Time	Type	Des

Wellbores

Wellbore Name	KO MD (ftKB)
Original Hole	



Daily Drilling Report

Report for: 8/26/2014
Report #: 3.0, DFS: 1.13
Depth Progress: 1,055.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192		Surface Legal Location 6-22-4-2		License # FEE	
Spud Date 6/9/2014 10:00		Date TD Reached (wellbore)		Rig Release Date 9/2/2014 06:00	
				Ground Elevation (ft) 4,935.00	
				Orig KB Elev (ft) 4,947.00	
Completion Type					
Weather RAINING OFF & ON		Temperature (°F) 66.0		Road Condition FAIR / LOC. MUDDY	
				Hole Condition Good	
Operation At 6am DRILLING & SLIDING W/ MWD @ 2075' 95 FPH				Operation Next 24hrs DRILL PROD. HOLE	
24 Hr Summary TEST BOPS PICK UP BHA , TRIP IN . CUT DRILLING LINE DRILL CEMENT THEN FORMATION					

Time Log

Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com
06:00	09:30	3.50	3.50	15	TEST B.O.P	TEST BOPS PIPE ; BLINES & CHOKE 3000 F/5 MINS ANULAR 1500 PSI F/ 10 MINS CASING 1500 F/ 30 MIN ALL OK
09:30	12:00	2.50	6.00	6	TRIPS	PICK UP BHA & DIR. TOOLS & TRIP IN HOLE
12:00	13:00	1.00	7.00	9	CUT OFF DRILL LINE	CUT DRILLING LINE
13:00	18:00	5.00	12.00	21	OPEN	TAG @ 890 DRILL PLUG CEMENT FLOAT & SHOE
18:00	00:00	6.00	18.00	2	DRILL ACTUAL	DRILLING F/ 1020 TO 1537 (86 FPH) 390 GAL 12 K ON BIT 122 TOTAL RPMS NO LOSSES
00:00	00:30	0.50	18.50	7	LUBRICATE RIG	RIG SERVICE
00:30	06:00	5.50	24.00	2	DRILL ACTUAL	DRILLING F/ 1537 TO 2075 (98 FPH) 390 GAL 14 -16 K ON BIT 122 TOTAL RPMS 40 BBL LOST TO HOLE

Mud Checks

1,100.0ftKB, 8/26/2014 17:00

Type Water	Time 17:00	Depth (ftKB) 1,100.0	Density (lb/gal) 8.80	Funnel Viscosity (s/qt)	PV Override (cP)	YP OR (lb/100ft²)
Gel 10 sec (lb/100ft²) 1.000	Gel 10 min (lb/100ft²) 1.000	Filtrate (mL/30min)	Filter Cake (1/32")	pH	Sand (%)	Solids (%)
				8.0	0.0	2.0
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L)	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)		

Drill Strings

BHA #1, Kick Off

Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8
Nozzles (1/32") 16/16/16/16/16	String Length (ft) 583.98	Max Nominal OD (in) 6.500			

String Components

SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP

Comment

Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)

Drilling Parameters

Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq
Original Hole	1,020.0	2,075.0	1,055.00	11.50	91.7	390	16	60	1,100.0	59	63	8,000.0

AFE Number 1753213US	
Start Depth (ftKB) 1,020.0	End Depth (ftKB) 2,075.0
Target Formation WASATCH	Target Depth (ftKB) 7,259.0
Last Casing String Surface, 1,013.0ftKB	
Daily Contacts	
Job Contact	Mobile
Floyd Mitchell	823-3608
DOUG HACKFORD	970-640-3882

Rigs

Capstar, 316

Contractor Capstar	Rig Number 316
Rig Supervisor JAKE	Phone Mobile 713-481-7601

<des>, <make>, <model>

Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...)
P (psi)	Slow Spd	Strokes (s...)
		Eff (%)

Mud Additive Amounts

Des	Field Est (Cost/unit)	Consumed
DAP	35.00	10.0
Engineering	450.00	1.0
Rental	50.00	1.0
Tax	1.00	25.0

Safety Checks

Time	Type	Des

Wellbores

Wellbore Name	KO MD (ftKB)
Original Hole	



Daily Drilling Report

Report for: 8/27/2014
Report #: 4.0, DFS: 2.13
Depth Progress: 1,750.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192		Surface Legal Location 6-22-4-2		License # FEE								
Spud Date 6/9/2014 10:00		Date TD Reached (wellbore)		Rig Release Date 9/2/2014 06:00								
				Ground Elevation (ft) 4,935.00								
				Orig KB Elev (ft) 4,947.00								
Completion Type												
Weather STILL RAIN OFF & ON		Temperature (°F) 62.0		Road Condition POOR								
				Hole Condition Good								
Operation At 6am DRILLING @ 3825' 70 FPH				Operation Next 24hrs DRILL 7 7/8 PROD. HOLE								
24 Hr Summary DRILL F/ 2075' TO 3825 STARTED LIGHT MUD UP AT 3500' BBG 456-757 UNITS CONNS 320-546 W/ A PEAK OF 1246 UNITS @ 3626 DRILLING 50% CLAY STONE & 50% SHALE												
Time Log												
Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com						
06:00	16:30	10.50	10.50	2	DRILL ACTUAL	DRILLING F/ 2075 TO 2949 (83 FPH) 390 GAL 14 -16 K ON BIT 122 TOTAL RPMS 80 BBL LOST TO HOLE						
16:30	17:00	0.50	11.00	7	LUBRICATE RIG	RIG SERVICE						
17:00	06:00	13.00	24.00	2	DRILL ACTUAL	DRILLING F/ 2949 TO 3825 (67 FPH) 390 GAL 14 -16 K ON BIT 122 TOTAL RPMS 130 BBLS LOST TO HOLE						
Mud Checks												
2,948.0ftKB, 8/27/2014 17:00												
Type water	Time 17:00	Depth (ftKB) 2,948.0	Density (lb/gal) 9.10	Funnel Viscosity (s/qt) 31	PV Override (cP) 1.0	YP OR (lbf/100ft²) 1.000						
Gel 10 sec (lbf/100ft²) 1.000	Gel 10 min (lbf/100ft²) 1.000	Filtrate (mL/30min)	Filter Cake (1/32")	pH 8.0	Sand (%) 0.1	Solids (%) 6.0						
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L) 11,000.000	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lbf/100ft²)						
Whole Mud Added (bbl)		Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)		Active Mud Volume (bbl)						
Drill Strings												
BHA #1, Kick Off												
Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8							
Nozzles (1/32") 16/16/16/16/16			String Length (ft) 583.98	Max Nominal OD (in) 6.500								
String Components SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP												
Comment Smith MDi616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)												
Drilling Parameters												
Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq
Original Hole	2,075.0	3,825.0	2,805.0 0	35.00	74.5	390	16	60	1,100.0	90	92	9,900.0

AFE Number 1753213US		
Start Depth (ftKB) 2,075.0		End Depth (ftKB) 3,825.0
Target Formation WASATCH		Target Depth (ftKB) 7,259.0
Last Casing String Surface, 1,013.0ftKB		
Daily Contacts		
Job Contact		Mobile
Floyd Mitchell		823-3608
DOUG HACKFORD		970-640-3882
Rigs		
Capstar, 316		
Contractor Capstar		Rig Number 316
Rig Supervisor JAKE		Phone Mobile 713-481-7601
<des>, <make>, <model>		
Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...)
P (psi)	Slow Spd	Strokes (s... Eff (%)
Mud Additive Amounts		
Des	Field Est (Cost/unit)	Consumed
DAP	35.00	14.0
Engineering	450.00	1.0
Hole Seal	21.00	8.0
Rental	50.00	1.0
Sea Mud	15.50	60.0
Tax	1.00	110.0
Safety Checks		
Time	Type	Des
Wellbores		
Wellbore Name	KO MD (ftKB)	
Original Hole		



Daily Drilling Report

Report for: 8/28/2014
Report #: 5.0, DFS: 3.13
Depth Progress: 1.150.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192		Surface Legal Location 6-22-4-2		License # FEE								
Spud Date 6/9/2014 10:00		Date TD Reached (wellbore)		Rig Release Date 9/2/2014 06:00								
				Ground Elevation (ft) 4,935.00								
				Orig KB Elev (ft) 4,947.00								
Completion Type												
Weather WARM		Temperature (°F) 78.0		Road Condition GOOD								
				Hole Condition Good								
Operation At 6am DRILLING @ 4975' 40 FPH				Operation Next 24hrs DRILL 7 7/8 PROD. HOLE								
24 Hr Summary DRILL F/ 3825 TO 4975 TOPPED THE TGR3 IN TARGET @ 4695' BGG 183 - 334 UNITS CONNS 338 - 559 & A PEAK OF 3224 @ 4270 DRILLING 40 % SH 40% SS & 20 % CLYST												
Time Log												
Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com						
06:00	16:00	10.00	10.00	2	DRILL ACTUAL	DRILLING F/ 3825 TO 4361 (44 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS 30 BBLS MUD LOST TO HOLE						
16:00	16:30	0.50	10.50	7	LUBRICATE RIG	RIG SERVICE						
16:30	06:00	13.50	24.00	2	DRILL ACTUAL	DRILLING F/ 4361 TO 4975 (45 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS ONLY LOST 97 BBLS OF MUD TO THE HOLE						
Mud Checks												
4,360.0ftKB, 8/28/2014 16:30												
Type WATER	Time 16:30	Depth (ftKB) 4,360.0	Density (lb/gal) 9.30	Funnel Viscosity (s/qt) 32	PV Override (cP) 5.0	YP OR (lb/100ft²) 4.000						
Gel 10 sec (lb/100ft²) 3.000	Gel 10 min (lb/100ft²) 5.000	Filtrate (mL/30min)	Filter Cake (1/32")	pH 8.5	Sand (%) 0.3	Solids (%) 5.8						
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L)	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)						
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)								
Drill Strings												
BHA #1, Kick Off												
Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8							
Nozzles (1/32") 16/16/16/16/16/16			String Length (ft) 583.98	Max Nominal OD (in) 6.500								
String Components SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP												
Comment Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)												
Drilling Parameters												
Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq
Original Hole	3,825.0	4,975.0	3,955.00	58.50	48.9	390	18	60	1,270.0	107	115	10,300.0

AFE Number 1753213US		
Start Depth (ftKB)	3,825.0	End Depth (ftKB) 4,975.0
Target Formation WASATCH	Target Depth (ftKB) 7,259.0	
Last Casing String Surface, 1,013.0ftKB		
Daily Contacts		
Job Contact	Mobile	
Floyd Mitchell	823-3608	
DOUG HACKFORD	970-640-3882	
Rigs		
Capstar, 316		
Contractor Capstar	Rig Number 316	
Rig Supervisor JAKE	Phone Mobile 713-481-7601	
<des>, <make>, <model>		
Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...)
P (psi)	Slow Spd	Strokes (s...)
		Eff (%)
Mud Additive Amounts		
Des	Field Est (Cost/unit)	Consumed
Aluminum Stear.	130.00	1.0
DAP	35.00	3.0
Engineering	450.00	1.0
Gel	7.50	140.0
Hole Seal	21.00	16.0
Pallet	20.00	3.0
Rental	50.00	1.0
Sea Mud	15.50	42.0
Shrink Wrap	20.00	3.0
Tax	1.00	167.0
Safety Checks		
Time	Type	Des
Wellbores		
Wellbore Name	KO MD (ftKB)	
Original Hole		



Daily Drilling Report

Report for: 8/29/2014
Report #: 6.0, DFS: 4.13
Depth Progress: 1,050.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192	Surface Legal Location 6-22-4-2	License # FEE
Spud Date 6/9/2014 10:00	Date TD Reached (wellbore)	Rig Release Date 9/2/2014 06:00
	Ground Elevation (ft) 4,935.00	Orig KB Elev (ft) 4,947.00

Completion Type				
Weather NICE	Temperature (°F) 81.0	Road Condition GOOD	Hole Condition Good	
Operation At 6am DRILLING @ 6025' 48 FPH		Operation Next 24hrs DRILL 7 7/8 DROD HOLE		
24 Hr Summary DRILL F/ 4975 TO 6025' TOPPED DOUGLAS CREEK @ 5523' BGG 133-423 CONNS 148-279 & PEAK GAS 1250 @ 5134' DRILLING 50% CLYS 50% SH				

Time Log						
Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com
06:00	16:00	10.00	10.00	2	DRILL ACTUAL	DRILLING F/ 4975 TO 5430' (46 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS LOST 67 BBLs OF MUD TO THE HOLE
16:00	16:30	0.50	10.50	7	LUBRICATE RIG	SERVICE RIG
16:30	06:00	13.50	24.00	2	DRILL ACTUAL	DRILLING F/ 5430 TO 6025 (44 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS LOST 124 BBLs OF MUD TO THE HOLE

Mud Checks						
5,342.0ftKB, 8/29/2014 14:00						
Type Water Base	Time 14:00	Depth (ftKB) 5,342.0	Density (lb/gal) 9.50	Funnel Viscosity (s/qt) 32	PV Override (cP) 5.0	YP OR (lb/100ft²) 5,000
Gel 10 sec (lb/100ft²) 3,000	Gel 10 min (lb/100ft²) 5,000	Filtrate (mL/30min)	Filter Cake (1/32")	pH 8.5	Sand (%) 0.3	Solids (%) 9.0
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L) 24,000.000	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)		

Drill Strings						
BHA #1, Kick Off						
Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8	
Nozzles (1/32") 16/16/16/16/16/16	String Length (ft) 583.98		Max Nominal OD (in) 6.500			

String Components SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP						
Comment Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)						

Drilling Parameters												
Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq
Original Hole	4,975.0	6,025.0	5,005.0 0	82.00	44.7	390	18	60	1,390.0	122	128	8,100.0 0

AFE Number 1753213US	
Start Depth (ftKB) 4,975.0	End Depth (ftKB) 6,025.0
Target Formation WASATCH	Target Depth (ftKB) 7,259.0

Daily Contacts	
Job Contact	Mobile
Floyd Mitchell	823-3608
DOUG HACKFORD	970-640-3882

Rigs	
Capstar, 316	
Contractor Capstar	Rig Number 316
Rig Supervisor JAKE	Phone Mobile 713-481-7601

<des>, <make>, <model>			
Pump #	Pwr (hp)	Rod Dia (in)	
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...	
P (psi)	Slow Spd	Strokes (s...	Eff (%)

Mud Additive Amounts		
Des	Field Est (Cost/unit)	Consumed
DAP	35.00	40.0
Engineering	450.00	1.0
Hole Seal	21.00	8.0
Sawdust	4.50	22.0
Tax	1.00	117.0
Trucking	1.00	800.0

Safety Checks		
Time	Type	Des

Wellbores	
Wellbore Name	KO MD (ftKB)
Original Hole	



Daily Drilling Report

Report for: 8/30/2014
Report #: 7.0, DFS: 5.13
Depth Progress: 950.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192	Surface Legal Location 6-22-4-2	License # FEE
Spud Date 6/9/2014 10:00	Date TD Reached (wellbore)	Rig Release Date 9/2/2014 06:00
		Ground Elevation (ft) 4,935.00
		Orig KB Elev (ft) 4,947.00
Completion Type		
Weather NICE	Temperature (°F) 78.0	Road Condition GOOD
		Hole Condition Good
Operation At 6am DRILLING @ 6975' 30 FPH	Operation Next 24hrs DRILL ON TO TD CIRC CLEAN SPOT KILL PILL POOH & LOG WELL	

24 Hr Summary

DRILL F/ 6025 TO 6975 TOPPED BLACK SHALE @ 5968' THE CASTLE @ 6205' UTELAND BUTTE @ 6485 & THE WASATCH @ 6650 BGG 195-282 CONNS 245-276 PEAK 1533 UNIT @ 6573' DRILLING 50% CLYST 30% SH 20% SS

Time Log

Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com
06:00	16:30	10.50	10.50	2	DRILL ACTUAL	DRILLING F/ 6025 TO 6457 (41 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS LOST 105 BBLs OF MUD TO THE HOLE
16:30	17:00	0.50	11.00	7	LUBRICATE RIG	RIG SERVICE
17:00	06:00	13.00	24.00	2	DRILL ACTUAL	DRILLING F/ 6457 TO 6975 (40 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS LOST 85 BBLs OF MUD TO THE HOLE

Mud Checks

6,264.0ftKB, 8/30/2014 12:00

Type Water Base	Time 12:00	Depth (ftKB) 6,264.0	Density (lb/gal) 9.50	Funnel Viscosity (s/qt) 30	PV Override (cP) 4.0	YP OR (lb/100ft²) 3,000
Gel 10 sec (lb/100ft²) 2,000	Gel 10 min (lb/100ft²) 3,000	Filtrate (mL/30min)	Filter Cake (1/32")	pH 8.5	Sand (%) 0.3	Solids (%) 9.0
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L) 30,000.000	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)		

Drill Strings

BHA #1, Kick Off

Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8
Nozzles (1/32") 16/16/16/16/16/16	String Length (ft) 583.98	Max Nominal OD (in) 6.500			

String Components

SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP

Comment

Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)

Drilling Parameters

Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq
Original Hole	6,025.0	6,975.0	5,955.0 0	105.5 0	40.4	390	18	60	1,400.0	136	143	7,800. 0

AFE Number 1753213US	
Start Depth (ftKB) 6,025.0	End Depth (ftKB) 6,975.0
Target Formation WASATCH	Target Depth (ftKB) 7,259.0

Daily Contacts

Job Contact	Mobile
Floyd Mitchell	823-3608
DOUG HACKFORD	970-640-3882

Rigs

Capstar, 316

Contractor Capstar	Rig Number 316
Rig Supervisor JAKE	Phone Mobile 713-481-7601

<des>, <make>, <model>

Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...)
P (psi)	Slow Spd	Strokes (s...)
		Eff (%)

Mud Additive Amounts

Des	Field Est (Cost/unit)	Consumed
Brine	7.50	300.0
DAP	35.00	16.0
Engineering	450.00	1.0
Hole Seal	21.00	5.0
Rental	50.00	1.0
Sawdust	4.50	28.0
Sea Mud	15.50	6.0
Tax	1.00	62.0

Safety Checks

Time	Type	Des

Wellbores

Wellbore Name	KO MD (ftKB)
Original Hole	



Daily Drilling Report

Report for: 8/31/2014
Report #: 8.0, DFS: 6.13
Depth Progress: 300.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192		Surface Legal Location 6-22-4-2		License # FEE	
Spud Date 6/9/2014 10:00		Date TD Reached (wellbore)		Rig Release Date 9/2/2014 06:00	
				Ground Elevation (ft) 4,935.00	
				Orig KB Elev (ft) 4,947.00	
Completion Type					
Weather NICE		Temperature (°F) 81.0		Road Condition GOOD	
				Hole Condition Good	
Operation At 6am LOGGING WELL W/ HALLIBURTON				Operation Next 24hrs FINNISH LOGGING RUN 5 1/2 CASING CEMENT NIPPLE BOPS DOWN CLEAN MUD PITS R.R.	
24 Hr Summary DRILL F/ 6975 TO 7275 T.D. BGG 79-268 CONNS 188-298 PEAK 2719 @ 7260 CIRC CLEAN SPOT KILL PILL POOH TIGHT @ 3800' CIRC CLEAN @ 3500' PULL ON OUT LOG WELL					

Time Log

Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com
06:00	19:00	13.00	13.00	2	DRILL ACTUAL	DRILLING F/ 6975 TO 7275 (23 FPH) 390 GAL 18 K ON BIT 122 TOTAL RPMS LOST 88 BBLS OF MUD TO THE HOLE
19:00	21:00	2.00	15.00	5	COND MUD & CIRC	PUMP SWEEP & CIRC 2 BOTTOMS UP SPOT 10.2 # KILL PILL THEN DRY JOB
21:00	23:30	2.50	17.50	6	TRIPS	POOH F/ LOGS UP TO 3500'
23:30	00:30	1.00	18.50	5	COND MUD & CIRC	CIRC 2 BOTTOMS UP (SHAKERS CLEAN)
00:30	03:30	3.00	21.50	6	TRIPS	PULL ON OUT LAY DOWN DIR. TOOLS
03:30	06:00	2.50	24.00	11	WIRELINE LOGS	HELD SAFETY MEETING RIG UP H.L.S. & LOG WELL

Mud Checks

7,077.0ftKB, 8/31/2014 11:00

Type Water Base	Time 11:00	Depth (ftKB) 7,077.0	Density (lb/gal) 9.50	Funnel Viscosity (s/qt) 30	PV Override (cP) 4.0	YP OR (lb/100ft²) 3.000
Gel 10 sec (lb/100ft²) 2.000	Gel 10 min (lb/100ft²) 3.000	Filtrate (mL/30min)	Filter Cake (1/32")	pH 8.5	Sand (%) 0.3	Solids (%) 9.0
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L) 30,000.000	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)		

Drill Strings

BHA #1, Kick Off

Bit Run 1	Drill Bit 7 7/8in, MDI616, JJ6889	Length (ft) 1.00	IADC Bit Dull 0-0-0---i-0-TD	TFA (incl Noz) (in²) 1.18	BHA ROP... 52.8
Nozzles (1/32") 16/16/16/16/16	String Length (ft) 583.98	Max Nominal OD (in) 6.500			

String Components

SMITH MDI616, Mud Motor, UBHO, NMDC, Drill Collar, HWDP

Comment

Smith MDI616 (Newsco MM,6.5" 7/8, 3.3 Stg. .16 Rev. 1.50° Bend)(6.375"x2.5"UBHO) (1-6.375"x2.375"NMDC)(6-6.125"x 2.375" DC)(10-4.5" HWDP)

Drilling Parameters

Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq.
Original Hole	6,975.0	7,275.0	6,255.0 0	118.5 0	23.1	390	18	60	1,400.0	140	145	7,800. 0

AFE Number 1753213US	
Start Depth (ftKB) 6,975.0	End Depth (ftKB) 7,275.0
Target Formation WASATCH	Target Depth (ftKB) 7,259.0
Last Casing String Surface, 1,013.0ftKB	

Daily Contacts

Job Contact	Mobile
Floyd Mitchell	823-3608
DOUG HACKFORD	970-640-3882

Rigs

Capstar, 316

Contractor Capstar	Rig Number 316
Rig Supervisor JAKE	Phone Mobile 713-481-7601

<des>, <make>, <model>

Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...
P (psi)	Slow Spd	Strokes (s... Eff (%)

Mud Additive Amounts

Des	Field Est (Cost/unit)	Consumed
Aluminum Stear.	130.00	2.0
Barite	10.65	144.0
DAP	35.00	17.0
Engineering	450.00	1.0
Hole Seal	21.00	20.0
Pallet	20.00	8.0
Rental	50.00	1.0
Sea Mud	15.50	192.0
Shrink Wrap	20.00	8.0
Tax	1.00	329.0

Safety Checks

Time	Type	Des

Wellbores

Wellbore Name	KO MD (ftKB)
Original Hole	



Daily Drilling Report

Report for: 9/1/2014
Report #: 9.0, DFS: 7.13
Depth Progress: 0.00

Well Name: DEEP CREEK 6-22-4-2E

UWI/API 43-047-54192	Surface Legal Location 6-22-4-2	License # FEE
Spud Date 6/9/2014 10:00	Date TD Reached (wellbore)	Rig Release Date 9/2/2014 06:00
		Ground Elevation (ft) 4,935.00
		Orig KB Elev (ft) 4,947.00
Completion Type		
Weather COOL	Temperature (°F) 66.0	Road Condition GOOD
		Hole Condition Good
Operation At 6am RELEASE RIG 0600 8/2/14		Operation Next 24hrs MOVE TO DEEP CREEK 16-22-4-2E RIG UP TEST BOP PICK UP BHA SPUD IN

24 Hr Summary

LOG WELL LOG TO 7260' LOG UP TO 1007' W/ TRIPLE COMBO PUSS GAMMA UP TO 200' / RUN 5 1/2 CASING TO 7260 CEMENT W/HALLIBURTON PUMP 10 BBL WATER /PUMP 160 SKS 10.5# 4.31 YIELD LEAD THEN 505 SKS 13.1# 1.66 YIELD TAIL CEMENT / 167 BBL WATER DISPLACEMENT BUMP PLUG @ 10 :55 500 PSI OVER 40 BBL CEMENT TO SURFACE FCP 1675 CLEAN UP & RIG DOWN NIPPLE DOWN BOP & CLEAN MUD PITS W/ BADGER

Time Log

Start Time	End Time	Dur (hr)	Cum Dur (hr)	Aty Code	Activity	Com
06:00	10:30	4.50	4.50	11	WIRELINE LOGS	LOG WELL W/ HALLIBURTON LOG TO 7260' RUN TRIPLE COMBO PUSS UP TO SURFACE PIPE 1007' GAMMA UP TO 200'
10:30	19:30	9.00	13.50	12	RUN CASING & CEMENT	RUN 159 FULL JTS 5 1/2 17# L80 CASING & 2 MARKERS LAND ON HANGER @ 7260'
19:30	23:30	4.00	17.50	12	RUN CASING & CEMENT	HELD SAFETY MEETING & RIG UP AND CEMENT W/ HALLIBURTON PUMP 10 BBL WATER /PUMP 160 SKS 10.5# 4.31 YIELD LEAD THEN 505 SKS 13.1# 1.66 YIELD TAIL CEMENT / 167 BBL WATER BUMP PLUG 10:"55 CIRC 40 BBL CEMENT TO SURFACE CLEAN UP & RIG DOWN
23:30	06:00	6.50	24.00	14	NIPPLE UP B.O.P	NIPPLE DOWN CLEAN MUD PITS W/ BADGER RELEASE RIG @ 0600 8/2/14

Mud Checks

<depth>ftKB, <dtm>

Type	Time	Depth (ftKB)	Density (lb/gal)	Funnel Viscosity (s/qt)	PV Override (cP)	YP OR (lb/100ft²)
Gel 10 sec (lb/100ft²)	Gel 10 min (lb/100ft²)	Filtrate (mL/30min)	Filter Cake (1/32")	pH	Sand (%)	Solids (%)
MBT (lb/bbl)	Alkalinity (mL/mL)	Chlorides (mg/L)	Calcium (mg/L)	Pf (mL/mL)	Pm (mL/mL)	Gel 30 min (lb/100ft²)
Whole Mud Added (bbl)	Mud Lost to Hole (bbl)	Mud Lost to Surface (bbl)	Reserve Mud Volume (bbl)	Active Mud Volume (bbl)		

Drill Strings

BHA #<stringno>, <des>

Bit Run	Drill Bit	Length (ft)	IADC Bit Dull	TFA (incl Noz) (in²)	BHA ROP...
Nozzles (1/32")		String Length (ft)		Max Nominal OD (in)	

String Components

Comment

Drilling Parameters

Wellbore	Start (ftKB)	End Depth (ftKB)	Cum Depth (ft)	Cum Drill Time (hr)	Int ROP (ft/hr)	Q Flow (gpm)	WOB (1000lbf)	RPM (rpm)	SPP (psi)	Drill Str Wt (1000lbf)	PU Str Wt (1000lbf)	Drill Tq

AFE Number 1753213US	
Start Depth (ftKB) 7,275.0	End Depth (ftKB) 7,275.0
Target Formation WASATCH	Target Depth (ftKB) 7,259.0
Last Casing String Production, 7,260.0ftKB	

Daily Contacts

Job Contact	Mobile
Floyd Mitchell	823-3608
DOUG HACKFORD	970-640-3882

Rigs

Capstar, 316

Contractor Capstar	Rig Number 316
Rig Supervisor JAKE	Phone Mobile 713-481-7601

<des>, <make>, <model>

Pump #	Pwr (hp)	Rod Dia (in)
Liner Size (in)	Stroke (in)	Vol/Stk OR (b...
P (psi)	Slow Spd	Strokes (s... Eff (%)

Mud Additive Amounts

Des	Field Est (Cost/unit)	Consumed
Barite	10.65	80.0
Engineering	450.00	1.0
Rental	50.00	1.0
Tax	1.00	30.0

Safety Checks

Time	Type	Des

Wellbores

Wellbore Name	KO MD (ftKB)
Original Hole	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: CRESCENT POINT ENERGY U.S. CORP		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 555 17th Street, Suite 750 , Denver, CO, 80202		8. WELL NAME and NUMBER: Deep Creek 6-22-4-2E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1586 FNL 1726 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 22 Township: 04.0S Range: 02.0E Meridian: U		9. API NUMBER: 43047541920000
PHONE NUMBER: 720 880-3621 Ext		9. FIELD and POOL or WILDCAT: UNDESIGNATED
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	OTHER: <input style="width: 100px;" type="text"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/21/2014	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME		
<input type="checkbox"/> SPUD REPORT Date of Spud:				
<input type="checkbox"/> DRILLING REPORT Report Date:				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Crescent Point Energy US Corp reports the first production of hydrocarbons from Deep Creek 6-22-4-2E on September 21st, 2014.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

October 09, 2014

NAME (PLEASE PRINT) Emily Kate DeGrasse	PHONE NUMBER 720 880-3644	TITLE Regulatory & Government Affairs Analyst
SIGNATURE N/A	DATE 10/8/2014	



6-22-4-2E Deep Creek

Well Name and Number:			
-----------------------	--	--	--

<u>1-16-4-2E Deep Creek</u>			
-----------------------------	--	--	--

Date First Produced:	9/21/2013	Test Date:	9/22/2013	Hours Tested:
----------------------	-----------	------------	-----------	---------------

Choke Size:	64/64	100	0	Casing Pressure:
-------------	-------	-----	---	------------------

Per Hour Rates:	Oil: Bbl/Hr	Gas: MCF/Hr	Water: Bbl/Hr
→	10.17	1	49.36

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: CRESCENT POINT ENERGY U.S. CORP		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 555 17th Street, Suite 750 , Denver, CO, 80202		8. WELL NAME and NUMBER: Deep Creek 6-22-4-2E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1586 FNL 1726 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 22 Township: 04.0S Range: 02.0E Meridian: U		9. API NUMBER: 43047541920000
PHONE NUMBER: 720 880-3621 Ext		9. FIELD and POOL or WILDCAT: UNDESIGNATED
COUNTY: UINTAH		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input checked="" type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 12/15/2014
<input type="checkbox"/> SPUD REPORT Date of Spud:	OTHER: <input style="width: 100px;" type="text"/>			
<input type="checkbox"/> DRILLING REPORT Report Date:				

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.
 Please see attached application to commingle production formations for the Deep Creek 6-22-4-2E.

Approved by the
 January 29, 2015
 Oil, Gas and Mining

Date: _____

By: Dark Duff

NAME (PLEASE PRINT) Valari Cray	PHONE NUMBER 303 880-3637	TITLE Drilling And Completion Tech
SIGNATURE N/A	DATE 12/15/2014	



Crescent Point

main / 720.880.3610
fax / 303.292.1562
toll free / 1.888.693.0020
555 17th Street, Suite 1800
Denver, Colorado
USA 80202

December 3, 2014

Utah Division of Oil, Gas & Mining
Attention: Dustin Doucet
1594 West North Temple, Suite 1120
Salt Lake City, Utah 84116

RE: Sundry Notices
Deep Creek 6-22-4-2E
Uintah County, UT

Dear Mr. Doucet:

Crescent Point Energy has submitted Sundry Notices to commingle production from the Wasatch and Green River formations in the subject well. Pursuant to the Utah OGM regulations, we have enclosed a copy of the Sundry Notice, a plat showing the owners of contiguous leases, as well as an affidavit confirming notice.

If you should have any questions regarding these Sundry Notices, please feel free to contact me at 303-382-6785.

Sincerely,

Jordan Wells
Landman

Enclosures

AFFIDAVIT OF NOTICE

Jordan Wells, of lawful age, after having first duly sworn upon his oath, disposes and states:

That he is employed by Crescent Point Energy U.S. Corp. ("Crescent Point") as a Landman. Crescent Point has submitted Sundry Notices to commingle production from the Wasatch and Green River formations in the following well within the Randlett Exploration and Development Agreement Area:

DEEP CREEK 6-22-4-2E:

SENW Section 22 T4S-R2E

That in compliance with the Utah OGM regulation R649-3-22, I have provided a copy of the Sundry Notice, via certified mail, to the owners (see listed below) of all contiguous oil and gas leases or drilling units overlying the pool.

Finley Resources Inc.
Attn: Zachary Archer
1308 Lake St.
Fort Worth, TX
76102


Broughton Petroleum Inc.
ATTN: Bill Wilson
PO Box 1389
Sealy, TX 77474

Kaiser-Francis Oil Company
Attn: Robert Wadley
P.O. Box 21468
Tulsa, OK.
74121-1468

Date: December 3, 2014

Affiant

Jordan Wells
Landman


A large, stylized handwritten signature in dark ink, likely belonging to Jordan Wells, is written over the signature line and extends upwards and to the right.



40 Acre Spacing Unit



Application for Commingling
Deep Creek 6-22-4-2E
12-9-2014



STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MININGAMENDED REPORT ☐ FORM 8
(highlight changes)

5. LEASE DESIGNATION AND SERIAL NUMBER:

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT or CA AGREEMENT NAME

8. WELL NAME and NUMBER:

9. API NUMBER:

10 FIELD AND POOL, OR WILDCAT

11. QTR/QTR, SECTION, TOWNSHIP, RANGE,
MERIDIAN:

12. COUNTY

13. STATE

UTAH

1a. TYPE OF WELL:

OIL WELL ☐GAS WELL ☐DRY ☐

OTHER

b. TYPE OF WORK:

NEW WELL ☐HORIZ. LATS. ☐DEEP-EN ☐RE-ENTRY ☐DIFF. RESVR. ☐

OTHER

2. NAME OF OPERATOR:

3. ADDRESS OF OPERATOR:

CITY

STATE

ZIP

PHONE NUMBER:

4. LOCATION OF WELL (FOOTAGES)

AT SURFACE:

AT TOP PRODUCING INTERVAL REPORTED BELOW:

AT TOTAL DEPTH:

14. DATE SPUDDED:

15. DATE T.D. REACHED:

16. DATE COMPLETED:

ABANDONED ☐READY TO PRODUCE ☐

17. ELEVATIONS (DF, RKB, RT, GL):

18. TOTAL DEPTH: MD

TVD

19. PLUG BACK T.D.: MD

TVD

20. IF MULTIPLE COMPLETIONS, HOW MANY? *

21. DEPTH BRIDGE MD

PLUG SET:

TVD

22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each)

23.

WAS WELL CORED?

NO ☐YES ☐

(Submit analysis)

WAS DST RUN?

NO ☐YES ☐

(Submit report)

DIRECTIONAL SURVEY?

NO ☐YES ☐

(Submit copy)

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)
(A)				
(B)				
(C)				
(D)				

27. PERFORATION RECORD

INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>
			Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL

29. ENCLOSED ATTACHMENTS:

☐ ELECTRICAL/MECHANICAL LOGS ☐ GEOLOGIC REPORT ☐ DST REPORT ☐ DIRECTIONAL SURVEY
☐ SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION ☐ CORE ANALYSIS ☐ OTHER: _____

30. WELL STATUS:

31. INITIAL PRODUCTION**INTERVAL A (As shown in item #26)**

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL B (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL C (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)**33. SUMMARY OF POROUS ZONES (Include Aquifers):**

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)

35. ADDITIONAL REMARKS (Include plugging procedure)

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) _____ TITLE _____

SIGNATURE _____ DATE _____

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation
- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

Job Number: 34338	State/Country: Utah/ USA
Company: Cresent Point	Declination: 11.0
Lease/Well: Deep Creek 6-22-4-2E	Grid:
Location: Deep Creek 6-22-4-2E	File name: C:\WINSERVE\ACCESS\34338.SVY
Rig Name: Capstar 316	Date/Time: 02-Sep-14 / 14:45
RKB: 18	Curve Name: As Drilled
G.L. or M.S.L.: 4937	

Newsco

WINSERVE SURVEY CALCULATIONS

Minimum Curvature Method

Vertical Section Plane .00

Vertical Section Referenced to offset from Wellhead: EW =.00 Ft , NS=.00 Ft

Rectangular Coordinates Referenced to Wellhead

Measured Depth FT	Incl Angle Deg	Drift Direction Deg	True Vertical Depth FT	N-S FT	E-W FT	CLOSURE Section FT	CLOSURE Distance Deg	CLOSURE Direction Deg/100	Dogleg Severity FT	Course Length
.00	.00	.00	.00	.00	.00	.00	.00	.00		
1062.00	1.00	140.90	1061.95	-7.19	5.84	-7.19	9.27	140.90	.09	1062.00
1190.00	2.10	163.80	1189.90	-10.31	7.20	-10.31	12.58	145.06	.97	128.00
1319.00	3.30	152.70	1318.75	-15.88	9.57	-15.88	18.54	148.94	1.01	129.00
1447.00	4.10	151.70	1446.49	-23.18	13.43	-23.18	26.79	149.93	.63	128.00
1575.00	4.50	152.50	1574.13	-31.67	17.91	-31.67	36.38	150.50	.32	128.00
1704.00	3.90	148.30	1702.78	-39.89	22.56	-39.89	45.82	150.51	.52	129.00
1832.00	3.50	150.20	1830.51	-46.98	26.78	-46.98	54.08	150.31	.33	128.00
1960.00	3.80	142.60	1958.25	-53.74	31.30	-53.74	62.19	149.78	.44	128.00
2088.00	3.50	141.10	2085.99	-60.15	36.33	-60.15	70.27	148.87	.25	128.00
2217.00	2.60	143.60	2214.81	-65.57	40.54	-65.57	77.09	148.27	.71	129.00
2345.00	2.60	140.20	2342.68	-70.14	44.12	-70.14	82.86	147.83	.12	128.00
2473.00	2.80	137.70	2470.53	-74.68	48.08	-74.68	88.82	147.22	.18	128.00
2602.00	2.20	136.10	2599.41	-78.80	51.92	-78.80	94.36	146.62	.47	129.00
2731.00	2.20	142.70	2728.32	-82.55	55.14	-82.55	99.27	146.26	.20	129.00
2859.00	2.30	135.00	2856.22	-86.32	58.44	-86.32	104.24	145.90	.25	128.00
2987.00	2.30	129.90	2984.12	-89.78	62.23	-89.78	109.24	145.27	.16	128.00
3116.00	2.50	140.90	3113.00	-93.63	65.99	-93.63	114.55	144.82	.39	129.00
3244.00	2.80	145.60	3240.87	-98.37	69.52	-98.37	120.46	144.75	.29	128.00
3373.00	4.30	156.60	3369.62	-105.41	73.22	-105.41	128.35	145.22	1.27	129.00

3501.00	4.50	156.60	3497.24	-114.42	77.12	-114.42	137.99	146.02	.16	128.00
3629.00	4.30	151.40	3624.86	-123.25	81.41	-123.25	147.71	146.55	.35	128.00
3758.00	4.20	147.20	3753.51	-131.46	86.28	-131.46	157.25	146.72	.25	129.00
3886.00	4.00	146.00	3881.18	-139.10	91.32	-139.10	166.40	146.72	.17	128.00
4014.00	4.40	163.00	4008.84	-147.50	95.25	-147.50	175.58	147.15	1.02	128.00

PAGE - 1

Measured Depth FT	Incl Angle Deg	Drift Direction Deg	True Vertical Depth FT	N-S FT	Vertical E-W FT	CLOSURE Section FT	CLOSURE Distance Deg	CLOSURE Direction Deg/100	Dogleg Severity FT	Course Length
4143.00	4.50	172.20	4137.45	-157.25	97.39	-157.25	184.96	148.23	.56	129.00
4271.00	4.40	173.00	4265.07	-167.10	98.67	-167.10	194.05	149.44	.09	128.00
4399.00	4.40	175.00	4392.69	-176.86	99.69	-176.86	203.02	150.59	.12	128.00
4528.00	4.10	178.70	4521.34	-186.40	100.23	-186.40	211.64	151.73	.31	129.00
4656.00	4.20	180.50	4649.00	-195.66	100.29	-195.66	219.87	152.86	.13	128.00
4785.00	3.90	179.30	4777.68	-204.77	100.30	-204.77	228.02	153.90	.24	129.00
4913.00	3.20	184.80	4905.43	-212.69	100.06	-212.69	235.05	154.81	.61	128.00
5041.00	3.70	205.80	5033.20	-219.96	97.96	-219.96	240.79	155.99	1.05	128.00
5169.00	3.10	198.70	5160.98	-226.96	95.05	-226.96	246.06	157.28	.57	128.00
5298.00	3.60	164.30	5289.77	-234.16	95.03	-234.16	252.71	157.91	1.58	129.00
5426.00	3.30	158.60	5417.54	-241.46	97.46	-241.46	260.39	158.02	.36	128.00
5555.00	3.00	156.90	5546.34	-248.03	100.14	-248.03	267.48	158.01	.24	129.00
5683.00	2.80	164.10	5674.18	-254.11	102.31	-254.11	273.94	158.07	.32	128.00
5811.00	2.60	167.00	5802.04	-259.95	103.82	-259.95	279.91	158.23	.19	128.00
5939.00	2.30	157.70	5929.92	-265.15	105.45	-265.15	285.35	158.31	.39	128.00
6067.00	2.50	161.70	6057.81	-270.18	107.30	-270.18	290.71	158.34	.20	128.00
6196.00	2.80	153.10	6186.67	-275.66	109.61	-275.66	296.65	158.32	.39	129.00
6324.00	2.90	151.90	6314.51	-281.31	112.55	-281.31	302.99	158.19	.09	128.00
6452.00	2.60	155.30	6442.37	-286.80	115.29	-286.80	309.10	158.10	.27	128.00
6580.00	2.60	155.90	6570.24	-292.09	117.69	-292.09	314.91	158.05	.02	128.00
6709.00	2.70	161.50	6699.10	-297.64	119.85	-297.64	320.86	158.07	.22	129.00
6837.00	3.00	160.60	6826.94	-303.66	121.91	-303.66	327.22	158.13	.24	128.00
6965.00	2.90	156.80	6954.77	-309.79	124.30	-309.79	333.80	158.14	.17	128.00
7093.00	3.10	158.00	7082.59	-315.98	126.87	-315.98	340.50	158.12	.16	128.00
7228.00	3.20	159.40	7217.39	-322.89	129.57	-322.89	347.92	158.14	.09	135.00
Projection to Bit										
7275.00	3.20	159.40	7264.32	-325.35	130.49	-325.35	350.54	158.15	.00	47.00

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: Fee
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: CRESCENT POINT ENERGY U.S. CORP		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: 555 17th Street, Suite 750 , Denver, CO, 80202		8. WELL NAME and NUMBER: Deep Creek 6-22-4-2E
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1586 FNL 1726 FWL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SENW Section: 22 Township: 04.0S Range: 02.0E Meridian: U		9. API NUMBER: 43047541920000
PHONE NUMBER: 720 880-3621 Ext		9. FIELD and POOL or WILDCAT: LELAND BENCH
COUNTY: UINTAH		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 12/12/2014 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. As requested, please find the attached Direction Drill and Exception Location Letter request along with a plat showing the surface and bottom hole location. Previous submitted letter only included an exception location request and a plat that only showed the surface hole		
<div style="text-align: center;"> Approved by the April 14, 2015 Oil, Gas and Mining </div> <div style="margin-top: 10px;"> Date: _____ By: <u>Derek Duff</u> </div>		
NAME (PLEASE PRINT) Kristen Johnson		PHONE NUMBER 303 308-6270
SIGNATURE N/A		TITLE Regulatory Technician
DATE 12/10/2014		



555 17th Street, Suite 1800
Denver, CO 80202
Phone: (720) 880-3610

April 14, 2015

State of Utah Division of Oil, Gas and Mining
Attention: Brad Hill
1594 West North Temple
Salt Lake City, UT 84116

RE: Directional Drilling (R649-3-11) & Exception Location Request (R649-3-3)
Deep Creek 6-22-4-2E
Surface Location: SENW of Section 22
1586' FNL & 1726' FWL
Target Location: SENW of Section 22
1986' FNL & 1995' FWL
T4S-R2E, USM
Uintah County, Utah

Dear Mr. Hill:

Pursuant to the filing of Crescent Point Energy U.S. Corp's (Crescent Point) Application for Permit to Drill regarding the above referenced well, and in accordance with Oil & Gas Conservation Rules R649-3-11 and R649-3-3, we are hereby submitting this letter as notice of our intention to directionally drill the captioned well and request that DOGM administratively grant an exception location for the Deep Creek 6-22-4-2E.

- For the Deep Creek 6-22-4-2E in order to be in the target window of 460' from the lot lines we needed to drift a minimum of 190' to the south of our SHL (but no more than 590' south). We ended up 325' south of our SHL putting us basically in the middle of the 40 acre lot north/south. We also needed to drift a minimum of 53' east of our SHL (but no more than 453' east). We ended up 130' east of our SHL.
- Crescent Point has notified and obtained consent from all other working interest owners within a 460' radius of the intended wellbore, which include Petroglyph Energy, Inc., Dusty Sanderson, Argo Energy Partners, Slover Minerals, LP, Kerr-McGee Oil and Gas Onshore LP, and Mark Chapman.

Therefore, based on the above stated information, Crescent Point requests the permit be granted pursuant to R649-3-11 and R649-3-3. If you have any questions or require further information, please don't hesitate to contact the undersigned at 303-382-6766 or by email at aellison@crescentpointenergy.com. Your consideration of this matter is greatly appreciated.

Sincerely,
Crescent Point Energy U.S. Corp

A handwritten signature in black ink, appearing to read 'Jordan Wells', is written over a horizontal line.

Jordan Wells
Landman - Crescent Point Energy
303-382-6785

43047541920000
SCANNED
LM 11/6/13


Please be advised that Petroglyph Energy, Inc does not have an objection to the directional drilling or exception location of the Deep Creek 2-22-4-2E.


By

PAUL POWELL, PRESIDENT
Name & Title

10/28/13
Date

Please be advised that Dusty Sanderson does not have an objection to the directional drilling or exception location of the Deep Creek 2-22-4-2E.


By

Shure Sanderson CEO
Name & Title

10-15-2013
Date

Please be advised that Argo Energy Partners does not have an objection to the directional drilling or exception location of the Deep Creek 2-22-4-2E.

Irene LaSusa
By


Irene LaSusa, President, Argo Energy Inc. GP
Name & Title

10/11/13
Date



Please be advised that Slover Minerals, LP does not have an objection to the directional drilling and surface location of the Deep Creek 2-22-4-2E.


By


Name & Title


Date

Please be advised that Kerr-McGee Oil and Gas Onshore LP does not have an objection to the directional drilling and surface location of the Deep Creek 2-22-4-2E.

A handwritten signature in blue ink, appearing to read "W. Chris Latimer", written over a horizontal line.

By


W. CHRIS LATIMER
LAND MANAGER

Name & Title

10/21/13

Date

Please be advised that Mark Chapman does not have an objection to the directional drilling and surface location of the Deep Creek 2-22-4-2E.


By

Mark A. Chapman, Owner
Name & Title

10-15-13
Date